



WEST BENGAL KHADI & VILLAGE INDUSTRIES BOARD

A Government of West Bengal Enterprise under
Micro, Small and Medium Enterprises and Textile Department
12, B.B.D.Bag, Kolkata – 700 001

Website: wbkvib.org.in / Web Portal: banglarkhadi.in



Memo No: 2065 /KB/ENGG/66/North 24 PGS District Office/2024-25

Date: 30.07.2025

TENDER REFERENCE No. KVIB/ENG-66/NIQ/065/2025-26 OF CHIEF EXECUTIVE OFFICER WEST BENGAL KHADI AND VILLAGE INDUSTRIES BOARD

The Chief Executive Officer, Khadi & village Industries Board, invites-tender for the work detailed below which are to be executed through Engineering Section of WBKVIB: -

Name of Work:	Geotechnical Soil investigation in land of proposed District Office of North 24 Parganas under WBKVIB.
Estimated Value:	₹ To be Quoted (Including All Taxes & LWS)
Earnest Money:	₹ 2% of Quoted Amount of L1(Lowest) Bidder (DD in favor of "WEST BENGAL KHADI AND VILLAGE INDUSTRIES BOARD" payable at "KOLKATA")
Completion:	60 Days from AOC
Location:	North 24 Parganas
Defect Liability Period:	3 months
Eligibility of Bidder:	Bona fide, Resourceful, Experience & Reliable Government Licensed Contractor / Agencies having adequate credentials in execution of similar nature of work or original Work under Govt. Department is Eligible through Pre-Qualification.

- ❖ Unsuccessful Tenderer will not have to pay the cost of tender documents for the purpose of participating in tendering, but the **successful bidder L1 (Lowest) Bidder will have to pay the cost of Tender Documents (2911) of 2 (two) A/PW/0/10C-35/10 Dated: - 26/07/2011 of secretary PWD Govt. of West Bengal**

Important Date & Time: -			
Publishing Date:			
Bid Submission Start Date:	30- July -2025	At	11.00 am
Bid Submission Closing Date:	18- Aug -2025	Up to	6.00 pm
Bid Opening Date (Technical):	19- Aug -2025	At	11.00 am
Bid Opening Date (Financial):	To be Notified		

General Instructions

❖ **Documents to be Submitted: -**

- Income Tax (Last Year)
- Pan Card.
- Latest professional Tax Paid Challan & P-Tax Enrollment Certificate, Professional Tax Payment Certificate.
- GST Return in Form No. 3B.
- Latest Valid Trade License.
- Credential Certificate.

❖ **Other Terms & Conditions: -**

- Pan Card, Professional Tax receipts Challan for the Year 2024-25, Current GSTIN registration Certificate along with current GST payment receipt to be accompanied with the Technical Bid document.
- No Mobilization advance and Secured Advance will be allowed.
- Security deposit @ 8% will be deducted from the running bill till completion of the work.
- Security deposit & Earnest Money Deposit will be released as per mentioned in Notice from the date of completion of the work and recommendation of Project Engineer.
- The Chief Executive Officer, WBKVIB reserves the right to cancel the NIT / EOI / NIQ due to unavoidable circumstances and no claim in this respect will be entertained.

- ❖ For any further query one can e-mail to ceowbkvib@gmail.com or call at 9674312318 According to clause 19 of 2911 (ii) contractor should have valid license under the contract labour (Regulation and Abolition) Act 1970 betaken commencement of work and continue it until completion.

❖ **Defect Liability Period: -**

03 (Three) Months	Full security deposit shall be refunded to the contractor on expiry of the time period from the actual date of completion of the work
12 (Twelve) Months	
36 (Thirty-Six) Months	i) 30% of the security deposit shall be refunded to the contractor on expiry of 2 (Two) years from the actual date of completion of the work. ii) The rest 70% of the security deposit shall be refunded to the contractor on expiry of 3 (Three) years from the actual date of completion of the work
60 (Sixty) Months	i) No security deposit shall be refunded to the contractor for 1st 3 (Three) years from the actual date of completion of work. ii) 30% of the security deposit shall be refunded to the contractor on expiry of 4 (Four) years from the actual date of completion of work. iii) The rest 70% of the security deposit shall be refunded to the contractor on expiry of 5 (Five) years from the actual date of completion of work
Interest free security	Full security deposit shall be refunded to the contractor after receiving the requesting letter from the contractor and 6 (Six) months after expiry of agreement with the Board

30/07/25
Chief Executive Officer
W.B. Khadi & V.I. Board

Memo No: 2065/167KB/ENGG/66/North 24 PGS District Office/2024-25

Date: 30.07.2025

Copy Forwarded for necessary information to:

1. The FA&CAO, WBKVIB
2. The AEO, WBKVIB
3. The PEO, WBKVIB
4. The Executive Engineer, WBKVIB
5. The District Officer, North 24 Parganas, WBKVIB
6. Office Website

30/07/25
Chief Executive Officer
W.B. Khadi & V.I. Board

Geotechnical Soil investigation in land of proposed District Office of North 24 Parganas

SL. No	Item Description	Quantity	Units	Rate with all GST & Taxes	TOTAL AMOUNT WITH ALL GST & TAXES
1.00	Mobilisation Charges of all tools & Plants along with accessories, material, labour, supervision etc. at site of work required in connection with boring and testing work, including setting up boring rigs and shifting to different Bore-hole points etc. and also including withdrawal of same from the site after completion of work, complete as per direction of Engineer-in-Charge b) Detailed Investigation, Payment will be made after successful completion of work	1.00	L.S		
2.00	Carriage of all Disturbed & Undisturbed Samples from site of work to the sional office or elsewhere including loading and unloading as per irection of Engineer-in-Charge. Detailed Investigation. (Some samples are to be kept at Sub-Division Office for Additional testing By the Engineer-in-Charge)	1.00	L.S		
3.00	Labour for making Bore-Holes of 150mm to 250mm dia, by any standard method to any depth below ground level/bed level in all kinds of soil like clay,silt, sand, stiff clay, mixed soils etc. except rocks (for the purpose of collecting Disturbed & Un disturbed soil samples, conducting Standard Penetration Test at suitable intervals etc.) including preparation and submission of bore-log as per IRC: 75 and 78 and Clause 2400 of Specifications for Road & Bridge Works (Sth Revision), Published by IRC, and also including hire charges of tools and plants complete as per the direction of Engineer-in-Charge. a) When Casing pipe is used to prevent collapse of bore hole (casing pipe to be finally withdrawn) (i) Depth Om to 10m: 20.00 mtr (2 X 10)	20.00	metre		
3.01	(ii) Depth greater than 10m and upto 20m(2 X 10)	20.00	metre		
4.00	A. Laboratory Investigation: i) Liquid Limit as per IS 2720 (Part-V).	12.00	Each		
4.01	ii) Plastic Limit as per IS 2720 (Part-V)	12.00	Each		
4.02	iii) Grain size analysis by Sieving as per IS 2720 (Part-IV)	12.00	Each		
4.03	iv) Gtain size analysis by Hydrometer Method as per IS 2720 (Part-(V).	12.00	Each		
4.04	v) Determination of Water Content as per IS 2720 (Part- II)	12.00	Each		
4.05	Vi) Determination of Specific Gravity as per IS	8.00	Each		
4.06	vii) Direct Shear Test as per IS 2720 (Part-xIII).	8.00	Each		
4.07	viii) Determination of Unconfined Compression Strength as per IS 2720 (Part-X)a) Undisturbed.	8.00	Each		
4.08	xv) Determination of Consolidation Properties as per 15 2720 (Part-XIV)	4.00	Each		
4.09	xvi) Tri-Axial Shear Test. a) Determination of Shear strength parameters of a specimen tested in Unconsolidated Undrained Tri-axial compression without measurement of pore water pressure as per 15 2720 (Part-XI)	8.00	Each		
4.10	8 Field Investigation, in) Collection of Samples from the bore hole made as per Ba (b) Disturbed	30.00	Each		
4.11	v) Collection of Undisturbed soil sample from the bore hole to be made by the concerned Division/Party at their cost. (i) 0.0m-10.0m	4.00	Each		
4.12	(ii) 10.0m-20.0m	2.00	Each		
4.13	vi) Standard Penetration Tests (SPT) by Split Spoon Sampler in the bore hole as per IS 2131 i) 0.0m-10.0m	12.00	Each		
4.14	(ii) 10.0m-20.0m	12.00	Each		
4.15	(iii) 10.0m-20.0m	6.00	Each		
5	Preparation and submission of report in 6 (Six) copies, giving all relevant information data like site plan, Bore log and water table, test results, calculations, discussions, suggestions and recommendations in respect of suitable foundation etc. including determination of silt factor calculation of waterways and complete design of foundation including analysis of Bearing Capacities and settlements in bound and presentable form complete as per direction of Engineer-in-Charge b) Detailed Investigation	1.00	L.S		
	Total Amount				

27/07/25
ASSISTANT ENGINEER (CIVIL)

WBKVIB

12, B.B.D. BAG, KOLKATA-700001

27/07/25
EXECUTIVE ENGINEER (CIVIL)

W. B. KHADI & V. I. BOARD

12, B.B.D. Bag., Kol-700001

29/7/25
Planning Cum-Evaluation Officer

W. B. KHADI & V. I. BOARD

30/07/25
Chief Executive Officer
W. B. KHADI & V. I. BOARD